





Material List

Item	Discription	Quantity	Comments
1	Floor Slab Concrete. 3,000 psi Compressive Strength	9 cubic yards	Fiberglass reinforcing recommended.
2	Footing Concrete. 3,000 psi Compressive Strength	7 cubic yards	Fiberglass reinforcing recommended.
3	Pier Concrete. 3,000 psi Compressive Strength	.5 cubic yards	Fiberglass reinforcing recommended.
4	#4 Steel Rebar continuous footing f/ ends.	Eight pieces 13'	Includes 12" laps.
5	#4 Steel Rebar continuous footing f/ sides.	Eight pieces 16'	Includes 12" laps.
6	#4 Steel Rebar cross-bar footing f/ mats.	114 pieces 16'	
7	#3 Steel Rebar Hoops.	114 pieces 16'	
8	#4 Steel Rebar Hooks.	40 pieces 16'	
9	1.5" Concrete Dobies with wire ties.	100	
10	Rebar Tie-Wire	2 rolls	Or, 1000 quick ties.
11	Concrete curing compond.	5 gallons	Spray on after concrete cures.

Side View Rebar Detail identical to End View Rebar Detail except with 29' 8" rebar lengths.

